

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-00436-00-01
Spot: SESESE Sec/Twnshp/Rge: 11-22S-18W
336 feet from S Section Line, 323 feet from E Section Line
Lease Name: REIFF Well #: 1
County: PAWNEE Total Vertical Depth: 4321 feet

Operator License No.: 34240
Op Name: NYE EXPLORATION LLC
Address: 231 N. BROADVIEW
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3790		WITH 2 SX CMT
CIBP		4050		WITH 2 SX CMT
SURF	8.625	1093		
PROD	4.5	4273	0	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2011 12:00 PM
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.
Proposal Rcvd. from: THOMAS G NYE Company: NYE EXPLORATION Phone: (316) 612-2242

Proposed Plugging Method: SET CIBP @ 4050' WITH 2 SX CMT. SET CIBP @ 3800' WITH 2 SX CMT. PERFORATE 4 1/2" @ 1130'. PUMP CMT DOWN THE 4 1/2" & CIRCULATE UP THE 8 5/8" X 4 1/2" ANNULUS.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2011 3:41 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4050' WITH 2 SX CMT ON TOP WITH A DUMP BAILER. SET CIBP @ 3790' WITH 2 SX CMT ON TOP WITH A DUMP BAILER. PERFORATED 4 1/2" @ 1130'. PUMPED 150 SX CMT DOWN THE 4 1/2" HAD CIRCULATION FOR 1/2 BARREL. PUMPED 150 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. MAXIMUM PRESSURE 500 PSIG. INITIAL SHUT IN PRESSURE 250 PSIG.

Perfs:

Top	Bot	Thru	Comments
4115	4120		
4071	4075		
3830	3830		

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY COPELAND

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED

AUG 19 2011

KCC DODGE CITY

RECEIVED

AUG 29 2011

KCC WICHITA

Form CP2/3