

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22317-00-00  
Spot: SWNESWSW Sec/Twnshp/Rge: 10-32S-39W  
653 feet from S Section Line, 827 feet from W Section Line  
Lease Name: MLP SIMONS B Well #: 1  
County: STEVENS Total Vertical Depth: 6150 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5730		
SURF	8.625	1603		WITH 415 SX CMT
PROD	5.5	6150	785	WITH 385 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/01/2011 9:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT AT PERFS. SHOOT 5 1/2" CASING & PUMP 50 SX CMT AT CASING STUB. 40 SX CMT AT 600'. FILL FROM 40' TO SURFACE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/01/2011 5:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMPED 200# HULLS & 25 SX CMT AT 5603'. CASING STRETCH AT 8". SHOT 5 1/2" CASING AT 785'. PUMPED MUD INTO CASING TO CIRCULATE HOLE. UNABLE TO CIRCULATE HOLE DUE TO CASING PUMPING OUT OF WELL AT 600 PSI. POH WITH CASING. END OF CASING HAD FLARED OUT. RIH W/TBG TO 785' & PUMPED 50 SX CMT. POH TO 600' & PUMPED 40 SX CMT. TOPPED OFF AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5944	5975		MORROW
5603	5606		MORROW

RECEIVED  
AUG 29 2011  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR RULE\*\* USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed

Jack MacLaskey  
(TECHNICIAN)

RECEIVED

AUG - 3 2011

KCC DODGE CITY

Form CP-2/3