

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21907-00-00
Spot: E2NWSW Sec/Twnshp/Rge: 20-17S-30W
1967 feet from S Section Line, 1049 feet from W Section Line
Lease Name: KEAVS Well #: 1
County: LANE Total Vertical Depth: 4610 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	224		WITH 160 SX CMT
PC		2243		WITH 330 SX CMT
PROD	4.5	4596	0	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2011 10:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 214-0330

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 150 # HULLS, GEL SPACER TO 2300' THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/09/2011 10:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

****CASING LEAK @ 1077-1108' SQUEEZED WITH 200 SX CMT. STILL LEAKING****
RUN TBG TO 3983' & PUMP 12 SX GELLED WATER, 35 SX CMT & 100# HULLS.
PULLED TBG TO 2300' & PUMP 170 SX CMT & 150# HULLS. CMT CIRCULATED.
PULLED TBG & TOP OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMP 5 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4362	4368		ALTAMONT
4018	4022		LKC

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED OIL WELL.

Plugged through: CSG

District: 01

Signed

Michael Maier
(TECHNICIAN)

RECEIVED

AUG 12 2011

KCC DODGE CITY

RECEIVED
AUG 29 2011
KCC WICHITA

Form CP-22