

2-8

4-032295

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-199-20,268-0000

NW NW NW /4 SEC. 27, 14, 42 W
4950 feet from S section line
4950 feet from E section line

Operator license# 31844

Lease: McKenna Trust Well # 1-27

Operator: Deka Exploration, Inc. &
Red Oak Energy
Address: P.O. Box 14057
Oklahoma City, OK 73113

County: Wallace 169.33

Well total depth 5210 feet
Conductor Pipe: 13 3/8 inch @ 422 feet
Surface pipe 8 5/8 Inch @ 0 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: 250 N. Water - Suite #300 - Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 8 Month: February Year: 1998

Plugging proposal received from: Bernie Meyer

Company: Murfin Drilling Company, Inc. Phone:

Were: Order 200 sxs 60/40 pozmix - 10% gel - 8 5/8" W.P.
Condition hole with no less than 36 vis mud.
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 1:30 P.M., Day: 8, Month: February, Year: 1998

Actual plugging report: Spot plugs with drill pipe. 13 3/8" set at 422' cwc.
1st. Plug at 2800' w/25 sxs.
2nd. Plug at 1800' w/100 sxs.
3rd. Plug at 475' w/40 sxs.
4th. Plug at 40' w/10 sxs. W.P.
15 sxs in rathole (circulated)
10 sxs in mousehole (circulated)

Remarks: Allied Cement Company
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [] / did not [X] observe the plugging.

Carl Goodrow
(agent)

Form CP-2/3

INVOICED
DATE FEB 23 1998

INV. NO. 50106

2-8 JUN 17 1998