

15-199-20278-00-00

4-070138

3-17

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-199-20,278-0000

SE SE SE /4 SEC. 16, 14 S, 42 W
330 feet from S section line
330 feet from E section line

Operator license# 31844

Lease: Waugh Trust Well # 1-16

Operator: Deka Exploration, Inc.

County: Wallace

Address: P.O. Box 14057
Oklahoma City, OK 73113

Well total depth 2755 ^{89.54} feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 470 feet

ABAND. oil well, Gas well, Input well, SWD., D&A X

Plugging contractor: Murfin Drilling, Inc. License# 30606

Address: 250 N. Water - Suite #300 - Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 17 Month: March Year: 1999

Plugging proposal received from: Bill Arbuckle

Company: Deka Exploration, Inc. Phone: 405-659-4164

Were: RTD 2755'. March 15, 1999 - Lost circulation. Pumped 1500 bbls of drilling mud and 550 sxs common cement. Still no returns. Operator wants to gravel pack to top cedar hills 2645' w/50 sxs common cement 3% c.c. Plug at 1875' w/50 sxs - 1525' w/50 sxs - 475' w/50 sxs 40' w/10 sxs.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 7:00 A.M. Day: 17, Month: March, Year: 1999

Actual plugging report: RTD 2755'. Gravel pack to 2650' w/50 sxs common cement with 3% c.c. Waited 2 hours. Tagged plug at 2467'. Filled hole with drilling mud.

2nd plug at 1875' w/50 sxs.

3rd plug at 1575' w/50 sxs.

4th plug at 475' w/50 sxs.

5th plug at 40' w/10 sxs. - one 8 5/8" wiper plug.

Rathole with 10 sxs.

Mousehole with 15 sxs.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 3826.8 GL

I did [] / did not [X] observe the plugging.

Rich Williams
(agent)

Form CP-2/3

INVOICED

DATE 4-2-99

INV. NO. 60756

03-8-1999