

4-100534

06-16-1998
DUP 1 1998

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, ROOM #2078
WICHITA, KANSAS 67202-3802

6-7

API number: 15- 199-20,276-0000

SW SW SE /4 SEC: 15- 14- 42 W
330 Feet from S (N/S) Line
2284 Feet from E (E/W) Line

Operator License# 31844

LEASE: Welsh Trust WELL # 1-15

Operator: Deka Exploration, Inc.

County: WALLACE 169.00

Address: P.O. Box 14057
Oklahoma City, OK
73113

Well total Dept 5200 feet
Conductor Pipe inch @ feet
Surface pipe 8 5/8 inch @ 481 feet

Aband. Oil Wel _____ Gas Well _____ Input Well _____ SWD: _____ D & A: X

Plugging contractor: Abercrombie RTD, Inc. License#: 30684

Address: Wichita, Ks.

Company to plug at: Hour: ? Day: _____ Month: _____ Year: _____

Plugging proposal received fro Walter Brown

Company: Abercrombie RTD, Inc. Phone: _____

Were:

- 1st plug @ 2800' with 25 sx
- 2nd plug @ 1870' with 100 sx
- 3rd plug @ 520 with 40 sx
- 4th plug @ 40' with wiper plug and 10sx40 sx
- Rat hole - 15 sx

Plugging proposal received by: David Wann

Pluggings operations attended by agent? All [], Part [], None [X]

Completed Hour: 5:15 AM Day: 7 Month: June Year: 1998

Actual plugging report:

Hole plugged as above.
Order 190 sacks of 60/40 Posmix w/6% gel and 1/4 lb flowcell per sack.


Remarks: Elevation: 3820 GL, Anhydrite top: 2803 feet Anhy. plug: Y

Dakota plug: Y Bottom plug in place N

Plugged through drill pipe Y

Arbuckle top Cemented by: Allied Cementing

I did [] did NOT [X] observe the plugging.


David Wann P.I.R.T. III
(agent)

INVOICED
DATE 6-18-98
50772