

To: **6 041081**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Operator: Union Pacific Resources Company  
Name & Address Box 7 MS 3407  
Fort Worth, Texas 76101-007

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Inc. License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: 10:45PM Day: 8 Month: Oct. Year: 19 89

Plugging proposal received from Bobby Cooper

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: Order 210 sks cement 60/40 poz 6% gel w/1/4# f.c.

Heavy mud between all plugs.

Pump cement down drill pipe.

Anhydrite 2818 - 50 Arb No.

Plugging Proposal Received by Dennis Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:45 PM Day: 8 Month: Oct. Year: 19 89

ACTUAL PLUGGING REPORT 25 sks at 2830' Anhy

100 sks at 1840'

40 sks at 700'

20 sks at 100'

15 sks in rathole 10 sks mousehole

Remarks: Halliburton Cementing  
(If additional description is necessary, use BACK of this form.)

(did X did not) observe this plugging.

**INVOICED**

DATE 11-2-89

INV. NO. 26322

10-8 DEC 15 1989

Signed Dennis L Hamel  
(TECHNICIAN)  
Dennis L. Hamel

10-8  
API NUMBER 15- 199-20, 179-00-00  
N/2 NE SE, SEC. 13, T 14 S, R 42 W/E  
2300 feet from S section line  
680 feet from E section line  
Lease Name Collins Farms Well # 1  
County Wallace 173.88  
Well Total Depth 5350 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 682' w/350 sks lite  
and 75 sks  
D&A Class A.

OCT 30 1989

10-30-1989