

4-032115

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-199-20,233-00-00

11-28

C N2 NW /4 SEC. 36, 14, 42 W
4620 feet from S section line
4080 feet from E section line

Operator license# 3581

Lease: Gebhards Well # 1-36

Operator: Red Oak Energy, Inc.

County: Wallace

Address: 200 W. Douglas- #510
Wichita, Kansas 67202

Well total depth 5280 171.60 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 571 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Murfin Drilling Company License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 28 Month: November Year: 1995

Plugging proposal received from: Matt

Company: Murfin Drilling Company Phone:

Were: Order 200 sxs 60/40 pozmix - 6% gel.
Allied Cement Company.
Condition hole with 36+ vis mud.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 3:00 P.M., Day: 28, Month: November, Year: 1995

Actual plugging report: Set plugs with drill pipe.

- 1st. Plug at 2850' w/25 sxs.
- 2nd. Plug at 1850' w/100 sxs.
- 3rd. Plug at 625' w/40 sxs.
- 4th. Plug at 40' w/10 sxs. W.P.
- Circulated 15 sxs in rathole.
- Circulated 10 sxs in mousehole.

DEC 13 1995
12-13-95
WICHITA, KANSAS

Remarks: Anhy. 2828' - 2860'.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO
Plugged through TUBING, CASING. Elevation: 3830 GL

I did / did not [X] observe the plugging.

Carl Goodrow
(agent)

DATE 11-13-95
44346
11-28

100