

4-060837

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-199-20,234-00-00

E2 E2 NE /4 SEC. 34, 14 S, 42 W
3960 feet from S section line
330 feet from E section line

2-15

Operator license# 3581

Lease: Hibbert Well # 1-34

Operator: Red Oak Energy, Inc.

County: Wallace

Address: 200 W. Douglas - #510
Wichita, Kansas 67202

Well total depth 5250 ^{170.62} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 611 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Murfin Drilling Company License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: 3:00 P.M. Day: 15 Month: February Year: 1996

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling Company Phone:

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
STATE CORPORATION COMMISSION

MAR 08 1996
03-08-1996

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:00 P.M., Day: 15, Month: February, Year: 1996

Actual plugging report:

- 1st. Plug at 2850' w/25 sxs. - Anhydrite to 2819' - 2854'.
- 2nd. Plug at 1900' w/100 sxs. - Dakota 1590' - 1890'.
- 3rd. Plug at 665' w/40 sxs. - Surface pipe to 611'.
- 4th. Plug at 40' w/10 sxs.
- Rathole with 15 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 3840 GL

I did [] / did not [X] observe the plugging.

(agent)

Form CP-2/3

45022
2-15-1996