

6-100489

3-8

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-199-20,214-00-00

W2 SE SE SW/4 SEC 33, 14 S, 42 W
330 feet from S section line
2150 feet from W section line

Operator license# 05030

Lease: HIBBERT Well # 1-33

Operator: Vess Oil Corporation

County: WALLACE

Address: 8100 East 22nd Street
North Building 300
Wichita, KS

Well total depth: 5230 feet
Conductor pipe: inch @ feet
Surface pipe: 8 5/8 inch @ 693 feet

169.97

67226

Abandoned Oil well: Gas Well: Input Well: SWD Well: D & A: X

Plugging contractor: ABERCROMBIE DRILLING, INC. License: 05422

Address: WICHITA, KANSAS

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: GRAY FISHER

Company: ABERCROMBIE DRILLING, INC. Phone:

Were: Spot all plugs through drill with heavy mud between all plugs.

1st plug @ 2825 feet with 25 sacks

Rat hole: 15 sacks

2nd plug @ 1900 feet with 100 sacks

Mouse hole: sacks

3rd plug @ 740 feet with 40 sacks

Wiper plug @ 40 feet

4th plug @ 40 feet with 10 sacks

5th plug @ feet with sacks

Plugging proposal received by: DAVID WANN

Plugging operations attended by agent? All [], Part [], None [X]

Completed: hour: 5:00 PM, Day: 8, Month: March, Year: 1994

Actual plugging report: Hole reported plugged as above

Order 190 sx 60/40 posmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 3858 G Anhydrite depth: 2822 feet, Anhy plug:
Dakota plugged: T Bottom hole plug in place
Plugged through drill pipe: T
Arbuckle: Cemented by: ALLIED CMT.

I did not [X] observe the plugging.

NOICED
40306

RECEIVED
STATE CORPORATION COMMISSION
APR 01 1994
04-01-1994
CONSERVATION DIVISION
Wichita, Kansas
(TECHNICIAN)

HO