

8-6

6 041207

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 199-20,190-0000  
S/2 SE, SSEC. 32, T 14 S, R 41 WAE

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Operator: Union Pacific Res. Co.  
Name & Address: Box 7 MS. 3407  
Fort Worth, Tx. 76101-007

336 feet from S section line  
660 feet from E section line  
Lease Name Schemm Well # 1  
County Wallace License Number 170.78  
Well Total Depth 5255 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 541 w/200 sks.

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number \_\_\_\_\_

Address Cheyenne Wells, Colorado

Company to plug at: Hour: 9:00AM Day: 6 Month: August Year: 19 90

Plugging proposal received from Jerry Mahan

(company name) U. P. R.Co. (phone) 06-17-1990

were: 5 1/2 casing set at 5253 w/250 sks cement; perf in morrow sand.

Ordered 235 sks 65/35 poz 8% gel w/1/4 lb. f.c. per sk cement.

Pressure test casing to 1000 lbs. : determine reepoint and cut off casing. Pump a balanced plug of 25 sks cement, half-in and half-out of casing: spotting balanced plugs seperated w/drilling mud as follows; 25 sks at 2800; 100 sks at 1850; to 1360; 40 sks at 640 - 450; 20 sks at 100 to surf.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:00PM Day: 6 Month: August Year: 19 90

ACTUAL PLUGGING REPORT MIRU w.l. corrolate and set c.i.b.p. at 5000'; P.O.O.H.

R.I.H. w/dump bailer dump 5 sks cement on c. i. b.p.: pressure test casing to 1000 lbs.: determine freepoint and cut off casing pump a balanced plug of 25 sks cement, half in and half out of casing; spotting balanced plugs seperated w/drilling mud as follows; 25sks at 2800; 100 sks at 1850; to 1360; 40 sks at 640-450; 20 sks at 100 ft. to surface.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (could not observe this plugging.)

DATE: 8-24-90  
INV. NO. 29083

J.L.S.

Signed Dennis L. Hamel DEPT. HEAD