

TO: ¹⁸²
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

. API Well Number: 15-199-20286-00-00
Spot: S2SWSE Sec/Twnshp/Rge: 35-15S-41W
330 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: AKERS TRUST Well Number: 1-35
County: WALLACE Total Vertical Depth: 5200 feet

Operator License No.: 3581
Op Name: RED OAK ENERGY, INC.
Address: P.O. BOX 783140 7701 E. KELLOGG STE
WICHITA, KS 67207

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 356
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 04/04/2001 6:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JIM RENNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

\$169.00

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 04/04/2001 9:00 AM

Witness Type: Plugging Operations Were Not Witnessed
KCC Agent: HERB DEINES

Actual Plugging Report:

1st6 Plug at 2725' w/25 sxs. Anhydrite 2688' - 2716'.
2nd. Plug at 1675' w/100 sxs. Dakota 1358' - 1658'.
3rd. Plug at 410' w/40 sxs. Surface pipe to 356'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

INVOICED
DATE 4-11-01
APR 11 2001

RECEIVED
STATE CORPORATION COMMISSION

APR 11 2001
04-11-01
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

