

12-14

83  
R

4- 060279

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-199-20,203 -00-00

SE NE SE /4 SEC. 26, 15 S, 42 W  
1650 feet from S section line  
330 feet from E section line

Operator license# 6593 Lease Nickelson well #1-26

Operator: Coastal Oil & Gas Corp. County Wallace

Address: 211 N. Robinson Well total depth 5300 feet  
Suite 1700 Conductor Pipe: 0 inch @ 0 feet  
Oklahoma City, OK 73102 Surface pipe 8 5/8 Inch @ 327 feet

172.25

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Murfin Drilling Company License# 6033

Address: Wichita, Kansas 67202

Company to plug at: Hour: 8:30P.M. Day: 14 Month: December Year: 91

Plugging proposal received from: Lawrence Mayworth

Company: Coastal Oil & Gas Corp. Phone: 405-239-7031

Were: Order 200 sxs. 60/40 posmix - 6% gel. - 1/4# flocele per sx.  
Space all plugs with heavy drilling and through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 8:30P.M., Day: 14, Month: December, Year: 91

Actual plugging report:     

- 1st. plug at 2760' with 25 sxs.
- 2nd. plug at 1780' with 100 sxs. - Dakota 1476' - 1776'.
- 3rd. plug at 380' with 40 sxs. - Surface pipe to 327'.
- 4th. plug at 40' with 10 sxs.

RECEIVED  
STATE CORPORATION COMMISSION

Rathole with 15 sxs.

Mousehole with 10 sxs.

DEC 18 1991  
12-18-91  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: B.J. Services Cementing.  
Elev. 3826'.

I did / did not [ X ] observe the plugging.

(agent)  
Form CP-2/3

INVOICED  
DATE 1-7-92  
34203  
12-14

File 9.