

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-071-20,504-00-00

LEASE NAME Baker 13-14

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1400 Ft. from S Section Line

4963 Ft. from E Section Line

SEC. 14 TWP. 16S RGE. 42 (XXXXXW)

COUNTY Greeley

Date Well Completed D&A

Plugging Commenced 05-03-90

Plugging Completed 05-03-90

LEASE OPERATOR Union Pacific Resources Company

ADDRESS P.O. Box 7 - MS 3407, Fort Worth, TX 76101-0007

PHONE# (817) 877-7956 OPERATORS LICENSE NO. 6417

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 05-03-90 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Did not produce Depth to Top \_\_\_\_\_ Bottom T.D. 5215'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To  | Size   | Put In | Pulled out |
|-----------|---------|------|-----|--------|--------|------------|
|           |         | 0    | 416 | 8 5/8" | 416'   | -0-        |
|           |         |      |     |        |        |            |
|           |         |      |     |        |        |            |
|           |         |      |     |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pump plugs as follows: Plug #1 2700' w/50. Plug #2 1900' w/80 sx. Plug #3 440' w/40 sx. Plug #4 40' w/10 sx behind wiper plug. Plug #5 w/15 sx in rathole. Plug #6 w/10 sx in mousehole. All cmt 60/40 Poz w/717 gel and 1/4# celloflake.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. \_\_\_\_\_

Address P.O. Box 1598, Liberal, KS 67901


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Union Pacific Resources Company

STATE OF Texas COUNTY OF Tarrant, ss.

Joy L. Prohaska (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J. L. Prohaska

(Address) P.O. Box 7 - MS 3407  
Fort Worth, Texas 76101-0007



RECEIVED  
STATE CORPORATION COMMISSION  
06-18-90  
JUN 18 1990  
AND SWORN TO before me this  
My Commission Expires  
MAY 23, 1990

before me this 15 day of June, 19 90

Sharon L. Cunningham  
Notary Public

My Commission Expires May 23, 1990