

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-071-20,365-00-00

LEASE NAME Garvey "P"

WELL NUMBER 5

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 7 TWP. 16S RGE. 42W (E) or (W)

COUNTY Greeley

Date Well Completed 5-10-85

Plugging Commenced 5-10-85

Plugging Completed 5-11-85

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Petroleum Inc.

ADDRESS P. O. Box 1255 Liberal, KS 67901

PHONE# (316) 624-1686 OPERATORS LICENSE NO. 5238

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? attached If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface Hole	Shale	Surface	1745	8-5/8"	1728'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Fluid to 2775', plug, 50 sx

Fluid to 1760', plug, 50 sx

Fluid to 880', plug, 50 sx

Fluid to 40', plug, 10 sx 15 sx in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor CHEYENNE DRILLING, INC. License STATE CORPORATION COMMISSION

Address P.O. Box 916 Garden City, Kansas 67846

STATE OF Kansas COUNTY OF Seward, ss.

Steve L. Phillips

(Employee of Operator) or WITNESS of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Steve Phillips

(Address) P. O. Box 1255 Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 21st day of May, 19 85

NOTARY PUBLIC - State of Kansas  
 JAMES R. HATFIELD  
 My Appt. Exp. 9/25/86

James R. Hatfield  
 Notary Public

My Commission Expires: \_\_\_\_\_

RECEIVED  
 MAY 22 1985  
 05-22-85  
 CONSERVATION DIVISION

DRILLER'S LOG

15-071-20365-00-00

Petroleum Inc.  
Garvey P #5  
1650 FNL, 330 FWL  
Section 7-T16S-R42W  
Greeley County, Kansas

Commenced: 5-02-85  
Completed: 5-11-85

Surface Casing: 1728' of 8-5/8"  
Cmtd w/550 sx HLC, 2% cc,  
250 sx Class H, 3% cc.

FORMATION

DEPTH

Surface Hole	0 - 1743
Sand, Shale	1743 - 2048
Shale, Lime	2048 - 2850
Lime, Shale	2850 - 3156
Shale, Lime	3156 - 3366
Shale, Clay	3366 - 3586
Shale, Lime	3586 - 3796
Lime, Shale	3796 - 3971
Shale, Lime	3971 - 4171
Lime, Shale	4171 - 4512
Shale, Lime	4512 - 4662
Lime, Shale	4662 - 4955
Lime, Shale, KC & Marmaton	4955 - 5120
Lime	5120 - 5300 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.


CHEYENNE DRILLING, INC.

*A. J. Jacques*  
A. J. Jacques

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 14<sup>th</sup> day of May, 19 85.

*Sharyn K. Coates*  
Sharyn K. Coates, Notary Public



RECEIVED  
STATE CORPORATION COMMISSION

MAY 22 1985

CONSERVATION DIVISION  
Wichita, Kansas