

TATE OF KANSAS
 TATE CORPORATION COMMISSION
 30 S. Market, Room 2078
 Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 15-071-20314-00-00

LEASE NAME Hale

WELL NUMBER 1

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 7 TWP. 16S RGE. 42 or (W)

COUNTY Greeley

Date Well Completed 5-5-84

Plugging Commenced 9-3-98

Plugging Completed 9-3-98

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Marlin Oil Corporation

ADDRESS P. O. Box 14630, OKC, OK 73113-0630

PHONE#(405) 478-1900 OPERATORS LICENSE NO. 9228

Character of Well D & A

Oil, Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on or about 7-15-98 (date)

by Steve Middleton (Dodge City) (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Dry Depth to Top Bottom T.O.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Water	5114	26	8.625	507	4
Kansas City-Lansing	Water	4168	70	4.500	5275	4
Kansas City-Lansing	Water	4222	90			
Kansas City-Lansing	Water	4554	57			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. CIBP set at 5050' and capped w/10' of cmt. Pressure tested 4 1/2x8 5/8" annulus to 250 psi. OK. Cmt'd down 4 1/2" csg w/50 sx cmt, 21 bbl gelled wtr, and 160 sx cmt. Hole did not load. Pmp'd 50 sx cmt, 21 bbls gelled wtr, and 160 sx cmt. Hole did not load. Pmp'd 50 sx cmt, 21 bbls gelled wtr, and 160 sx cmt. Hole loaded and pressured up. Cut off 8 5/8" and 4 1/2" csg.

Name of Plugging Contractor Allied Cementing Co. License No.

Address P. O. Box 31, Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Marlin Oil Corporation

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

W. R. Lynn (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 14630, OKC, OK 73113-0630

SUBSCRIBED AND SWORN TO before me this 2nd day of October, 19 98

[Signature]
 Notary Public

My Commission Expires: June 30, 2003

USE ONLY ONE SIDE OF EACH FORM