

RECEIVED
KANSAS CORPORATION COMMISSION

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

DEC 16 1997

12-16-1997

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

CONSERVATION DIVISION
API # WICB71-20,680-DD-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Red Oak Energy, Inc. KCC LICENSE # 03581
(owner/company name) (operator's)

ADDRESS 200 W Douglas, #510 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-9925

LEASE Lobmeyer WELL# 1-33 SEC. 33 T. 17S R. 42 (East/West)

SE - SE - NW - SPOT LOCATION/OQQO COUNTY Greeley

2310 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2330 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 276.61' CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 3836'/3841' T.D. 5300 PBDT _____ ANHYDRITE DEPTH 2650
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING 1st plug at 2650' with 50 sks, 2nd plug at 1700' with 80

sks, 3rd plug at 800' with 40 sks, 4th plug at 300' with 50 sks, 5th plug at 40'

with 10 sks, 15 sks in rat hole. Cemented with 245 sks 60/40 pos, 6% gel, 1/4# floeal per sk.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Enclosed

If not explain why? _____ N/A

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Walter Brown PHONE# (316) 855-7063

ADDRESS Box 1139 City/State Cimarron, KS 67835

PLUGGING CONTRACTOR Abercromble RTD, Inc. KCC LICENSE # 30684
(company name) (contractor's)

ADDRESS 150 N. Maine, #801, Wichita, KS 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12-1-97 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)