

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15 071 - 20,558 ~~0000~~ Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Convest Energy Corporation KCC LICENSE # 31673 ^{4/97}
(owner/company name) (operator's)

ADDRESS P.O. Box 309, #6 Spoon Drive CITY McCook

STATE NE ZIP CODE 69001 CONTACT PHONE # (308) 345-2480

LEASE Young WELL# 2-22 SEC. 22 T. 16S R. 42 (East/West)

C. S/2 SE SPOT LOCATION/QQQQ COUNTY Greeley

660 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1320 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 364' CEMENTED WITH 235 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 5220' CEMENTED WITH 550 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 5070' - 5078'

ELEVATION 3828' T.D. 5220' PBD 5165' ANHYDRITE DEPTH 2724'
(~~Ex~~/K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Pump 25 sks 60/40 Pozmix 6% gel mixed with 100# cotton seed hulls, 30 bbls. gell spacer, 150 sks 60/40 Pozmix 6% gel down casing. Pump 50 sks 60/40 Pozmix 6% gel down 8 5/8" X 4 1/2" annulus.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? yes

If not explain why? Logs were sent in with ACO-1

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

John Mondero PHONE# () 308-345-2480

ADDRESS P.O. Box 309 City/State McCook, NE 69001

PLUGGING CONTRACTOR Allied Cementing KCC LICENSE# _____
(company name) (contractor's)

ADDRESS _____ PHONE # () _____

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) As soon as approved

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR, OR AGENT

DATE: 04/11/97 AUTHORIZED OPERATOR/AGENT: John Mondero
(signature)

RECEIVED
KANSAS CORPORATION COMMISSION
APR 11 11:55 AM '97
04-11-97



15-071-20558-00-00

Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

April 14, 1997

Convest Energy Corporation
P O Box 309 #6 Spoon Drive
McCook NE 69001

Young #2-22
API 15-071-20,558
660 FSL 1320 FEL
Sec. 22-16S-42W
Greeley County

Dear John Mondero,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760