

4-032192

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-12

API Number: 15-199-20,196-00-00

S2 NW SE /4 SEC. 25, 15, 42 W
1650 feet from S section line
1980 feet from E section line

Operator license# 6593

Lease: Charles Well # 1-25

Operator: Coastal Oil & Gas Corporation

County: Wallace

Address: Nine Greenway Plaza
Houston, Texas 77046

Well total depth 5300 172.25 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 336 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Schlumberger License# -

Address: Houston, Texas 77046

Company to plug at: Hour: A.M. Day: 12 Month: December Year: 1996

Plugging proposal received from: Jayne Leuterman - Don DeHerrera

Company: Coastal Oil & Gas Corporation Phone:

Were: Order 300 sxs 35/65 pozmix - 6% gel - 300# hulls.

RCW
12-17-96

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:45 A.M., Day: 12, Month: December, Year: 1996

Actual plugging report: 8 5/8" set at 336' w/260 sxs. cwc. 5 1/2" set at 5300' with 450 sxs. D.V. at 1878' with 560 sxs cement. P.B.T.D. 5155'. Prod. Perfs 5004' - 5204'. Squeezed 5 1/2" with 50 sxs cement with 300# hulls, followed with 2700# gel, followed with 250 sxs cement to 95# P.S.I. Held.

Tested backside with 1 1/2 bbl to Max. P.S.I. 1500#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Any plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED

DATE JAN 02 1997

WV. NO. 47205

12-12 FEB 17 1997