

12-17

4-020059

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-199-20,225-00-00
N2 NW NE /4 SEC. 21, 15 S, 42 W
4950 feet from S section line
1993 feet from E section line

Operator license# 3581

Lease: Rother Farms Well #1-21

Operator: Red Oak Energy, Inc.

County: Wallace

Address: 200 W. Douglas, #510
Wichita, Ks 67202

Well total depth 5250 feet ^{170.63}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 399 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Abercrombie R.T.D. License# 30684

Address: 150 N. Main, Suite 801, Wichita KS 67202-1383

Company to plug at: Hour: Day: 17 Month: December Year: 1994

Plugging proposal received from: Gary Fisher

Company: Abercrombie R.T.D. Phone: 316 262 1841

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2820 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1835 feet with 100 sacks

3rd plug @ 450 feet with 40 sacks

4th plug @ 40 feet with 10 sacks

STATE CORPORATION COMMISSION
RECEIVED
FEB 24 1995
CONSERVATION DIVISION

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:30am, Day: 17, Month: December, Year: 1994

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 3885 GL

I did / did not X observe the plugging. Ken Kuhn

(agent)

DATE 2-27-98

WV. NO. 42271