

4-061199

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

9-30

API Number: 15-199-20,110-00-00

NW SW /4 SEC. 17 , 15 S, 42 W
1980 feet from S section line
4620 feet from E section line

Operator license# 5144

Lease: Akers "D" Well # 1

Operator: Mull Drilling Company, Inc.

County: Wallace

Address: P.O. Box 2758
Wichita, Kansas 67201

Well total depth 5350 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 2617/10 feet

173.88

Aband. oil well , Gas well X, Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc.

Kelso see attached
License# 31539

Address: 312 S. Main - Chase, Kansas 67524-0209

Company to plug at: Hour: 4:00 P.M. Day: 30 Month: September Year: 1999

Plugging proposal received from: Mike Kelso

Company: Mike's Testing & Salvage Phone: 316-938-2943

Were: Order 250 sxs 60/40 posmix - 10% gel with hulls.
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour 5:00 P.M., Day: 30, Month: September, Year: 1999

Actual plugging report: 8 5/8" to 716' w/325 sxs. 5 1/2" to 5338' w/155 sxs. Perfs at 5096' - 5108'. Sanded to 5045' and spotted 5 sxs cement with dump bailer. Checked stretch and found that well had been two staged. TOC in annulus at 50'. Holes in casing between Cedar Hill and Anhydrite. Established injection rate and pumped 225 sxs cement with 500# hulls. Pressured up to 50#.

Remarks: Allied Cementing.

Condition of casing in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 3915 GL

I did[] / did not[X] observe the plugging.

INVOICED

DATE 10-15-99

INVOICE NO. 60699

Herb Deines
(agent)

OK RECEIVED Form CP-2/3
STATE CORPORATION COMMISSION

OCT 12 1999
10-12-99
CONSERVATION DIVISION
Wichita Kansas

(Handwritten mark)