

6-100498

12-9

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-199-20,224-00-00

NW NW SW/4 SEC 05, 15 S, 42 W
2292 feet from S section line
330 feet from W section line

Operator license# 03581

Lease: JOHANNES Well # 1-5

Operator: Red Oak Energy, Inc.

County: WALLACE

Address: 200 West Douglas
Suite 510
Wichita, KS
67202

Well total depth: 5280 feet 171.60
Conductor pipe: inch @ feet
Surface pipe: 8 5/8 inch @ 653 feet

Abandoned Oil well: Gas Well: Input Well: SWD Well: D & A: X

Plugging contractor: ABERCROMBIE DRILLING License: 30684

Address: WICHITA, KANSAS

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: GARY FISHER

Company: ABERCROMBIE DRILLING Phone:

Were: Spot all plugs through drill with heavy mud between all plugs.

1st plug @ 2840 feet with 25 sacks

Rat hole: 15 sacks

2nd plug @ 1850 feet with 100 sacks

Mouse hole: sacks

3rd plug @ 700 feet with 40 sacks

Wiper plug @ 40 feet

4th plug @ 40 feet with 10 sacks

5th plug @ feet with sacks

Plugging proposal received by: DAVID WANN

Plugging operations attended by agent? All[], Part[], None[X]

Completed: hour: 10:00 AM, Day: 9, Month: December, Year: 1994

Actual plugging report: Hole reported plugged as above

Order 190 sx 60/40 posmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 3900 G Anhydrite depth: 2839 feet, Anhy. 26.9 g: T
Dakota plugged: T Bottom hole plug in place (A/E/N): N
Plugged through drill pipe: T
Arbuckle: Cemented by: ALLIED

I did[] / did not[X] observe the plugging.

[Signature]
(TECHNICIAN)

INVOICED

DATE 12-12-94
NO. 41903

12-12-94
RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS