

6-050130\_

2-25

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-199-20,215-0000  
E2 SE SE /4 SEC. 2, 15 S, 42 W  
660 feet from S section line  
330 feet from E section line

Operator license# 5030 Lease Walker Trust well # 1-2

Operator: Vess Oil Corporation County Wallace

Address: 810 E 22nd Street Well total depth 5200 feet <sup>169.00</sup>  
North Building #300 Conductor Pipe:      inch @      feet  
Wichita, Kansas Surface pipe 8 5/8 Inch @ 706 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Abercrombie Drilling License# 5422

Address: Wichita, Kansas

Company to plug at: Hour: AM Day: 25 Month: February Year: 1994

Plugging proposal received from: Gary Fischer

Company: Abercrombie Drilling phone:                     

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2820 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1790 feet " 100 " Mousehole: NA sacks

3rd plug @ 760 feet " 40 "

4th plug @ 40 feet " wiper plug & 10sx

Plugging Proposal Received by: Bruce D. Basye

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 6:00 AM, Day: 25, Month: February, Year: 1994

Actual plugging report: Hole reported plugged as above.  
Order 190 sx 60/40 pozmix w/ 6% gel and 2sx celloflake or flowcel.

Remarks: Elevation: 3837 GL, Anhydrite depth: 2804 - 2832 feet

Did not penetrate Arbuckle, cemented by Allied

I did[      ] / did not[ X ] observe the plugging.

*03-03-94*  
*ED*  
COMMISSION  
*3-03-1994*  
Bruce D. Basye Geologist  
(agent)  
Conservation Division  
Wichita, Kansas  
Form CP-2/3

INVOICED

DATE 3-8-94  
INV. NO. 40086

HD