

1080301

TO: STATE CORPORATION COMMISSION

API NUMBER 15-071-20,643-00-00  
C SW SEC. 23, T 16 S, R 40 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CHANCE HEIRS WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY

98.96

OPERATOR LICENSE # 31916

WELL TOTAL DEPTH 3045 FEET

OPERATOR: HB OPERATING, INC.

PRODUCTION CSG: SIZE 4 1/2" @ 3050' WITH SX <sup>top cmt @ 800'</sup>

NAME AND ADDRESS PO BOX 15163  
AMARILLO, TX 79105

SURFACE CASING: SIZE 8 5/8" @ 258' WITH SX <sup>circulated to surface</sup>

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR SWIFT SERVICES, INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 07 MONTH: 04 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DAVE OLSON

(COMPANY NAME) SWIFT SERVICE, INC (PHONE) 785-798-2300

WERE: PERFS AT 2942-60, 2968-77 CIBP @ 2938 2 SX CMT. PERFS AT 2875-2922. CIBP @ 2800 2 SX PERFS AT 1538-40. CIBP @ 1490' 2 SX CEMENT.

SET CIBP @ 1490' WITH 2 SX CEMENT. PEAK WIRELINE PERFORATED @ 780'. SWIFT SERVICES LOADED HOLE AND ANNULUS HAD GOOD BLOW, STARTED CEMENT PUMPED 200 SX CEMENT. CIRCULATED TO SURFACE. SHUT IN.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 12:15 PM DAY: 07 MONTH: 04 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

SET CIBP @ 1490' WITH 2 SX CEMENT. PEAK WIRELINE PERFORATED AT 780', SWIFT SERVICES LOADED HOLE AND ANNULUS HAD GOOD BLOW. STARTED CEMENT. PUMPED 200 SX CEMENT. CIRCULATED TO SURFACE. SHUT IN.

RECEIVED  
04-12-2000  
APR 12 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INVOICED  
SIGNED Kevin D Strube  
DATE 4/17/00 (TECHNICIAN)  
06/547  
FORM CP-2/3