

1 060855

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,421-00-00

NW SE NE, SEC. 32, T 16 S, R 41 W
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9860

Lease Name Johnson Well # 1

Operator: Castle Resources

County Greeley 172.25

Name & Address R. R. 1, Box 90

Well Total Depth 5300 Chester feet

Hays, KS 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 358

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor R & C Drilling Co., Inc. License Number 9087

Address P. O. Box 296, Hays, KS 67601

Company to plug at: Hour: 9:00 am Day: 14 Month: June Year: 19 86

Plugging proposal received from John Wise

(company name) R & C (phone) 913-625-4548

Elevation 3774'

were: to fill hole with heavy mud and spot plugs through drill pipe Anhydrite 2697-2727

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug through the Cheyenne Dakota with 100 sx cement

3rd plug at 380' with 40 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:15 am Day: 14 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2728' with 50 sx cement, 2nd plug at 1580' with

100 sx cement, 3rd plug at 380' with 40 sx cement, 4th plug from 40' to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1986

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix by Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE JUN 23 1986

INV. NO. 14186

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 6 month 2 day 86 year

API Number 15-071-20,421-00-00

OPERATOR: License # 9860 Castle Resources R.R. 1 Box 90 Hays, Kansas 67601 Jerry Green 913-625-9023

NW SE NE Sec. 32 Twp. 16 S, Rg. 41 West 3630 990 Ft. from South Line of Section 990 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 9087 R & C Drilling Co., Inc. P.O. Box 296, Hays, Kansas 67601

Nearest lease or unit boundary line 990 feet County Greely

Lease Name Johnson Well # 1

Well Drilled For: Oil Gas OWWO Well Class: Infield Pool Ext. Wildcat Type Equipment: Mud Rotary Air Rotary Cable

Ground surface elevation 3774 feet MSL Domestic well within 330 feet: yes no Municipal well within one mile: yes no

Depth to bottom of fresh water 200 Depth to bottom of usable water 1700

If OWWO: old well info as follows:

Surface pipe by Alternate: 1 2 X Surface pipe planned to be set 350

Operator Well Name Comp Date Old Total Depth

Conductor pipe required Projected Total Depth 5300

Formation

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 5-19-86 Signature of Operator or Agent Title as agent

For KCC Use:

Conductor Pipe Required 240 feet; Minimum Surface Pipe Required 240 feet per Alt. X

This Authorization Expires 11-19-86 Approved By 5-19-86

More in 6-2-86 set 350 of 8 5/8 RCH/100HR

NW SE NE Sec. 32 Twp. 16 S, Rg. 41 West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Any feet depth with 20 30 sxs of 60-40 poz
2nd plug @ Sand Chey Dakota feet depth with 100 sxs of 60-40 poz
3rd plug @ 320 380 feet depth with 40 40 sxs of 60-40 poz
4th plug @ 40 feet depth with 10 sxs of solid bridge 60-40 opz
5th plug @ feet depth with sxs of
(2) Rathole with 10 sxs (b) Mousehole with sxs

FUSHER John Wise TD 5300 FORMATION 6 besten SURFACE PIPE 358 @ 8 5/4 ANHYDRITE 2697-2227 ELEVATION 3774 STARTING TIME & DATE COMPLETION TIME & DATE 11:15am 6/14/86 1st PLUG @ 2728 FT. W/ 50 SX 2nd PLUG @ 1580 FT. W/ 100 SX 3rd PLUG @ 380 FT. W/ 40 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 10 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Halliburton TECHNICIAN

RECEIVED STATE CORPORATION COMMISSION JUN 23 1986 CONSERVATION DIVISION Wichita, Kansas