

1041347

TO: STATE CORPORATION COMMISSION

5-6

API NUMBER 15-071-20,708-00-00
130'N W/2 SW SEC. 28, T 16 S, R 41 W

CONSERVATION DIVISION - PLUGGING SECTION 1450 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME FTIA WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY 172.32

OPERATOR LICENSE # 4767

WELL TOTAL DEPTH 5302 FEET

OPERATOR: RITCHIE EXPLORATION, INC PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 783188 SURFACE CASING: SIZE 8 5/8" @ 313' WITH SX

ADDRESS WICHITA, KS 67278-3188

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MURFIN DRILLING COMPANY, INC LICENSE NUMBER 30606

ADDRESS 250 N WATER, SUITE 300, WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 4:15 AM DAY: 06 MONTH: 05 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM JIM RENNER

(COMPANY NAME) MURFIN DRILLING COMPANY, INC (PHONE) 316-267-3241

WERE:

1ST PLUG AT 2697 WITH 50 SX CEMENT. 2ND PLUG AT 1850' WITH 80 SX CEMENT.

3RD PLUG AT 925' WITH 50 SX CEMENT. 4TH PLUG AT 340' WITH 40 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT.

6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH

10 SX CEMENT. PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 8:30 AM DAY: 06 MONTH: 05 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2697' WITH 50 SX CEMENT. 2ND PLUG AT 1850' WITH 80 SX CEMENT.

3RD PLUG AT 925' WITH 50 SX CEMENT. 4TH PLUG AT 340' WITH 40 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT.

6TH PLUG TO CIRCULATE RAT HOLE WITH 15SX CEMENT.

7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLOW SEAL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

COMMISSION SIGNED

Signature of Stephen J. Pfeifer (TECHNICIAN)

DATE MAY 19 1999

INV. NO. 60961

Stamp: MAY 13 1999

Handwritten initials