

To: 1 11-25
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 071-20,682-00-00
App. SW SW, SEC. 28, T 16 S, R 41 W/X
560 feet from S section line
568 feet from WX section line

R

TECHNICIAN'S PLUGGING REPORT
Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address: P.O. Box 783188
Wichita, KS 67278

Lease Name FTIA Well # 1
County Greeley 172.25
Well Total Depth 5300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 273

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684
Address 150 N. Main, Ste. 801, Wichita, KS 67202

Company to plug at: Hour: 8:45 a.m. Day: 25 Month: 11 Year: 19 97

Plugging proposal received from Walter Brown
(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 2700' with 50 sx cement, 2nd plug at 1800' with 80 sx cement,
3rd plug at 900' with 40 sx cement, 4th plug at 300' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)



Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:45 p.m. Day: 25 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2710' with 50 sx cement, 12-02-97
2nd plug at 1800' with 80 sx cement,
3rd plug at 900' with 40 sx cement,
4th plug at 300' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby acknowledge and agree to pay for this plugging.

Signed  (TECHNICIAN) 

DATE DEC 10 1997

INV. NO. 49626
11-25

EFFECTIVE DATE: 10-26-97
DISTRICT # 1
SSA? Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL 071-20,682-0000
Must be approved by the X.C.C. five (5) days prior to commencing well

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Expected Spud Date 11 8 97
month day year

Spot appr. SW SW Sec. 28 Twp. 16 S. Rg. 41 West

OPERATOR: License # 4767
Name: Ritchie Exploration, Inc.
Address: P.O. Box 783188
City/State/Zip: Wichita, Kansas 67278
Contact Person: Julie Stout
Phone: (316) 691-9500

560 feet from South North line of Section
568 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License #: 30684
Name: Abercrombie RTD, Inc. Rig #4

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Greeley
Lease Name: FTIA Well #: 1
Field Name: WC

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OUVG ... Disposal X Wildcat ... Cable
... Seismic: ... # of Holes ... Other

Is this a Prorated/Spaced Field? ... yes X no
Target Formation(s): MORROW
Nearest lease or unit boundary: 560'

If OUVG: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Ground Surface Elevation: 3763 est. feet MSL
Water well within one-quarter mile: ... yes X no
Public water supply well within one mile: ... yes X no

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Depth to bottom of fresh water: 240
Depth to bottom of usable water: 1800
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 260 MIN.
Length of Conductor pipe required: none

Projected Total Depth: 5300'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well ... farm pond X other

DWR Permit #: _____
Will Cores Be Taken?: ... yes X no
If yes, proposed zone: _____

Exp. 4/21/98

AFFIDAVIT

260' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Walter
SPUD DATE 11-13-97 INIT. mlw
LENGTH SURFACE PLANNED 260'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 273 CONDUCTOR
ANHYDRITE T- B- 2704 ELEVATION
TD 5300 FORMATION _____
RAN PIPE @ DV TOOL ALT II DONE
_____ SX _____ SX Y N
Arbuckle Plug @ _____ Ft. W/ _____ SX
Hug./Council @ _____ Ft. W/ _____ SX
Anhydrite Base @ 2700 Ft. W/ 50 SX
1/2 Base Anyh. @ 1800 Ft. W/ 80 SX
1/2, 1/2 Plug @ 900 Ft. W/ 40 SX
Bottom Surface @ 300 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ _____ SX
WATER WELL _____ SX (Irr. Well Pond _____)
TECHNICIAN SM DATE 11-24-97 Hauling
TYPE OF CEMENT 60/40/67 1/4 Flowm
STARTING TIME 8:45 (AM/PM) DATE 11-25-97
COMPLETION TIME 12:45 (AM/PM) DATE 11-25-97
CEMENT COMPANY Alford