

1041383

TO: STATE CORPORATION COMMISSION

API NUMBER 15-071-20,719-00-00
100'E C NE NW NE SEC. 6, T 16 S, R 41 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1550 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME KUDER WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY 166.08

OPERATOR LICENSE # 8541 12/22 WELL TOTAL DEPTH 5110 FEET

OPERATOR: PETEX, INC. PRODUCTION CSG: SIZE " FEET

NAME AND ADDRESS 4175 S FARM RD. 193 ROGERSVILLE, MO 65742 SURFACE CASING: SIZE 8 5/8" @ 380' WITH SX

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MURFIN DRILLING COMPANY, INC LICENSE NUMBER 30606

ADDRESS 250 N WATER, SUITE 300, WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 3:30 AM DAY: 22 MONTH: 12 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM BERNIE

(COMPANY NAME) MURFIN DRILLING COMPANY, INC (PHONE) 316-267-3241

WERE:

1ST PLUG AT 2721' WITH 50 SX CEMENT. 2ND PLUG AT 1950' WITH 80 SX CEMENT.

3RD PLUG AT 975' WITH 50 SX CEMENT. 4TH PLUG AT 410' WITH 50 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 8:00 AM DAY: 22 MONTH: 12 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG AT 2721' WITH 50 SX CEMENT. 2ND PLUG AT 1950' WITH 80 SX CEMENT.

3RD PLUG AT 975' WITH 50 SX CEMENT. 4TH PLUG AT 410' WITH 50 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED [Signature] (TECHNICIAN)
STATE CORPORATION COMMISSION
FORM CP-2/3-8385
INVOICED
DATE 1/25/00
NO. 06/177
RECEIVED
STATE CORPORATION COMMISSION
JAN 25 2000
01-25-00