

5-8

1110139

API NUMBER 15- 071-20,472-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE SE, SEC. 31, T 17 S, R 42 W/E

330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5152

Lease Name Smith Well # 1

Operator: Lee Banks
Name & Address 200 West Douglas, Suite 550
Wichita, KS 67202

County Greeley 173.06

Well Total Depth 5325 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 381

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 12 a.m. Day: 8 Month: 5 Year: 1989

Plugging proposal received from Rodney Farr

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2648' with 50 sx cement, 2nd plug at 1350' with 100 sx cement,

3rd plug at 410' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by James R. Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:15 a.m. Day: 8 Month: 5 Year: 1989

ACTUAL PLUGGING REPORT 1st plug at 2648' with 50 sx cement,

2nd plug at 1350' with 100 sx cement,

3rd plug at 410' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

STATE CORPORATION COMMISSION
MAY 10 1989
05-10-1989
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 5-11-89

INV. NO. 24752
5-8

Signed James R. Kapp (TECHNICIAN)

15 - 071-20,472-00-00

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 5 month 1 day 1989 year
 SE SE SE Sec 31 Twp 17 S, Rg 42 East West

OPERATOR: License # 5152
 Name: Lee Banks
 Address: 200 W. Douglas Suite 550
 City/State/Zip: Wichita, Kansas 67202
 Contact Person: Lee Banks
 Phone: 267 0783

330 feet from South line of Section
330 feet from East line of Section
 (Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 6033
 Name: Murfin Drilling Company

County: Greeley
 Lease Name: Smith Well #: 1
 Field Name: WC
 Is this a Prorated Field? yes no
 Target Formation(s): Morrow
 Nearest lease or unit boundary: 330'
 Ground Surface Elevation: 3865 feet MSL
 Domestic well within 330 feet: yes no
 Municipal well within one mile: yes no
 Depth to bottom of fresh water: 280'
 Depth to bottom of usable water: 1550'
 Surface Pipe by Alternate: 1 2
 Length of Surface Pipe Planned to be set: 350'
 Length of Conductor pipe required: none
 Projected Total Depth: 5300'
 Formation at Total Depth: Mississippian
 Water Source for Drilling Operations:
 well farm pond other

Well Drilled For: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 OAWO Disposal Wildcat Cable
 Seismic; # of Holes

If OAWO: old well information as follows:
 Operator: _____
 Well Name: _____
 Comp. Date: _____ Old Total Depth _____


Directional, Deviated or Horizontal wellbore? yes no
 If yes, total depth location: _____

DWR Permit #: _____
 Will Cores Be Taken? yes no
 If yes, proposed zone: _____
 200' Alt. II Req.

PUSHER Rod Farr
 TD 5325 FORMATION Miss
 SURFACE PIPE 381 @ 8 5/8
 ANHYDRITE _____ ELEVATION _____
 STARTING TIME & DATE 12:00 mid 5-8-89
 COMPLETION TIME & DATE 3:15 AM
 1st PLUG @ 2648 FT. W/ 50 SX
 2nd PLUG @ 1350 FT. W/ 100 SX
 3rd PLUG @ 410 FT. W/ 40 SX
 4th PLUG @ 40 FT. W/ 10 SX
 RAT HOLE CIRCULATED W/ 15 SX
 MOUSE HOLE CIRCULATED W/ 10 SX
 WATER WELL PLUGGED W/ _____ SX
 CEMENT COMPANY Alized
 TECHNICIAN D.K.

SPUN
4-28-89
350-8 5/8"

RECEIVED
 STATE OF KANSAS
 CONSERVATION COMMISSION
 MAY 10 1989
 05-10-1989
 CONSERVATION DIVISION
 Wichita, Kansas



6 months or effective date, Spud date: _____ Agent: _____

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACO-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.