

To: 1 080110  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-6  
API NUMBER 15- 071-20,553-00-00  
NW SE NW, SEC. 19, T. 17 S, R. 42 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 30775

Operator: Savant Resources, Inc.  
Name & Address 216 16th St., Suite 1250  
Denver, CO 80202

1450 feet from N & section line  
1450 feet from W & section line  
Lease Name Kohn Well # 1-19  
County Greeley 170.62  
Well Total Depth 5250 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 365

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382  
Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 7 p.m. Day: 5 Month: 12 Year: 19 91

Plugging proposal received from Phil Lloyd  
(company name) Cheyenne Drilling, Inc. (phone) 316-277-2062

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2670'  
1st plug at 2750' with 50 sx cement, 2nd plug at 1750' with 80 sx cement,  
3rd plug at 925' with 50 sx cement, 4th plug at 400' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris  
(TECHNICIAN) X

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 7 a.m. Day: 6 Month: 12 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2750' with 50 sx cement,  
2nd plug at 1750' with 80 sx cement,  
3rd plug at 925' with 50 sx cement,  
4th plug at 400' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Halliburton.  
(if additional description is necessary, use BACK of this form.)

I (did) not observe this plugging.

DATE 12-12-91  
INV. NO. 34483

Signed Case Morris  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 12 1991  
12-11-1991  
CONSERVATION DIVISION  
Wichita Kansas

EFFECTIVE DATE: 11-24-91  
DISTRICT #  
SEAL Yes X No

State of Kansas  
NOTICE OF INTENTION TO DRILL 071-20,553-00-00 ALL BLANKS MUST BE FILLED  
Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date November 25 1991  
month day year

Spot NW SE NW Sec 19 Twp 17 S, Rg 42 West

OPERATOR: License # 30775  
Name: Savant Resources, Inc.  
Address: 216 16th Street, Suite 1250  
City/State/Zip: Denver, CO 80202  
Contact Person: Patterson Shaw  
Phone: (303) 592-1905

1450 feet from South / North line of Section  
1450 feet from East West line of Section  
IS SECTION REGULAR X IRREGULAR?

CONTRACTOR: License #: unknown at this time  
Name: *Cherry and Dewey*

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Greeley  
Lessee Name: Kohn Well #: 1-19  
Field Name: Wildcat  
Is this a Prorated/Spaced Field? yes X no  
Target Formation(s): Morrow  
Nearest lease or unit boundary: 975'  
Ground Surface Elevation: 3837 feet MSL  
Water well within one-quarter mile: yes X no  
Public water supply well within one mile: yes X no  
Depth to bottom of fresh water: 250  
Depth to bottom of usable water: 1760  
Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 350 ft  
Length of Conductor pipe required: None  
Projected Total Depth: 5200 ft  
Formation at Total Depth: Mississippian Keyes  
Water Source for Drilling Operations: well X farm pond other  
DWR Permit #:   
Will Cores Be Taken?: yes X no  
If yes, proposed zone:   
270' Alt. II Req.

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Enh Rec ... Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWWO ... Disposal X Wildcat ... Cable  
... Seismic: ... # of Holes ... Other  
If OWWO: old well information as follows:  
Operator:   
Well Name:   
Comp. Date: ... Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, true vertical depth:   
Bottom Hole Location:   
Exp. 5/19/92

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

553

Pusher *Phil Loynd*  
SPUD DATE 11-26-91 INIT. *SK*  
LENGTH SURFACE PLANNED 350  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 7/8" @ 350' CONDUCTOR  
ANHYDRITE T- 2470 B- ELEVATION  
TD 5250 FORMATION

RAN PIPE @ DV TOOL ALT II DONE  
SX Y N  
Arbuckle Plug @ Ft. W/ SX  
Hug./Council @ Ft. W/ SX  
Anhydrite Base @ 2750 Ft. W/ 50 SX  
1/2 Base Anyh. @ 1750 Ft. W/ 80 SX  
1/2, 1/2 Plug @ 925 Ft. W/ 50 SX  
Bottom Surface @ 400 Ft. W/ 50 SX  
40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond Hauling)  
TECHNICIAN *CS* DATE 12-5-91  
TYPE OF CEMENT 60/40 62 1/4 # F. I.  
STARTING TIME 7: (AM/PM) DATE 12/5  
COMPLETION TIME 7: (AM/PM) DATE 12/6  
CEMENT COMPANY *Ballentine*