

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-071-20,548-00-00

LEASE NAME Myers

WELL NUMBER 1-19

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 19 TWP. 17S RGE. 42 (E) or (W)

COUNTY Greeley

Date Well Completed 9/9/91

Plugging Commenced 9/9/91

Plugging Completed 9/9/91

LEASE OPERATOR Savant Resources Inc.

ADDRESS 216 16th Street, Suite 1250, Denver, CO 80202

PHONE# (303) 592-1905 OPERATORS LICENSE NO. 30775

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 9, 1991 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation N/A Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE OF KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
		0	357	8 5/8	357	0

10-07-1991
OCT 07 1991
CORPORATION DIVISION
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Cement plugs set 2700' - 2600' 50 sxs 15 sxs rat hole
1800' - 1600' 80 sxs 10 sxs mouse hole
370' - 320' 40 sxs All cement 60/40 Pozmix w/ 6% gel
40' - 0' 10 sxs Set using balanced plug method

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Cheyenne Drilling Co. License No. 05382

Address P.O. Box 916, Garden City, Kansas 67846

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Savant Resources Inc.

STATE OF Colorado COUNTY OF Denver, ss.

Patterson Shaw, President

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

Patterson Shaw, President

(Address) 216 16th St. Suite 1250 Denver, CO 80202

SUBSCRIBED AND SWORN TO before me this 4th day of October, 19 91

[Signature]
Notary Public

My Commission Expires: 6/25/95 Susan K. Dominish

19 17 42W

15-071-20548-00-00

RECEIVED
STATE CORPORATION COMMISSION

K C C

DRILLERS LOG

SEP 13 1991

SEP 16 1991

CONSERVATION DIVISION
Wichita, Kansas

SAVANT RESOURCES, INC.
MYERS #1-19
SECTION 19-T17S-R42W
GREELEY COUNTY, KANSAS

COMMENCED: 08-31-91
COMPLETED: 09-09-91

SURFACE CASING: 348' OF 8 5/8"
CMTD W/80 SX PREM PLUS LT. WT, 2% C.C.,
1/4#/SX FLO-CELE; TAILED IN W/
150 SX PREM PLUS, 2% C.C., 1/4#/SX FLO-CELE

FORMATION	DEPTH
SURFACE HOLE	0- 357
SAND & SHALE	357-1587
RED BED	1587-2500
SHALE & LIME	2500-2920
LIME & SHALE	2920-3270
SHALE & LIME	3270-3679
LIME & SHALE	3679-3773
SHALE & LIME	3773-4114
LIME & SHALE	4114-4682
SHALE & LIME	4682-4884
LIME & SHALE	4884-4915
SHALE & LIME	4915-5246
LIME & SHALE	5246-5376
SHALE & LIME	5376-5460 RTD

I DO HEREBY CERTIFY THAT THE FOREGOING STATEMENTS ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.


CHEYENNE DRILLING, INC.

A. J. Jacques

A. J. JACQUES

STATE OF KANSAS :ss:

SUBSCRIBED AND SWORN TO BEFORE ME THIS 11TH DAY OF SEPTEMBER, 1991.



Becky J. Whetstone
BECKY J. WHETSTONE, NOTARY PUBLIC