

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION

WELL COMPLETION OR RECOMPLETION FORM
ACO-1 WELL HISTORY

DESCRIPTION OF WELL AND LEASE

Operator: License # 5238
Name Petroleum Inc
Address P.O. Box 1255
City/State/Zip Liberal, KS 67901

Purchaser Koch Oil Co.
Wichita, KS

Operator Contact Person Steve Phillips
Phone 316-624-1686

Contractor: License # 5382
Name Cheyenne Drilling

Wellsite Geologist Bob Posey
Phone 316-624-5919

Designate Type of Completion

New Well Re-Entry Workover

Oil SWD Temp Abd
 Gas Inj Delayed Comp.
 Dry Other (Core, Water Supply etc.)

If OWWO: old well info as follows:

Operator
Well Name
Comp. Date Old Total Depth

WELL HISTORY

Drilling Method:

Mud Rotary Air Rotary Cable

6/27/85 7/6/85 7/27/85
Spud Date Date Reached TD Completion Date

5270' 5209'
Total Depth PBD

Amount of Surface Pipe Set and Cemented at 1741 feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set... feet
If alternate 2 completion, cement circulated from... feet depth to... w/... SX cmt

API NO. 15-071-20,369-00-00

County Greeley

NW NW NW Sec 7 Twp 16S Rge 42 East West

4950 Ft North from Southeast Corner of Section
4950 Ft West from Southeast Corner of Section
(Note: Locate well in section plat below)


Lease Name Garvey, Inc. "P" Well # 6

Field Name Stockholm, Southwest

Producing Formation Morrow

Elevation: Ground 3890 KB 3898

Section Plat



WATER SUPPLY INFORMATION

Disposition of Produced Water: Disposal Repressuring
Docket #

Questions on this portion of the ACO-1 call:

Water Resources Board (913) 296-3717

Source of Water:
Division of Water Resources Permit #

Groundwater... Ft North from Southeast Corner (Well) ... Ft West from Southeast Corner
Sec Twp Rge East West

Surface Water... Ft North from Southeast Corner (Stream, pond etc)... Ft West from Southeast Corner
Sec Twp Rge East West

Other (explain) The Hub of Syracuse (purchased from city, R.W.D. #)

INSTRUCTIONS: This form shall be completed in duplicate and filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within 90 days after completion or recompletion of any well. Rule 82-3-130 and 82-3-107 apply.

Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form. See rule 82-3-107 for confidentiality in excess of 12 months.

One copy of all wireline logs and drillers time log shall be attached with this form. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.


Signature Steven L. Phillips

Title Dist. Prod. Supt. Date 8/14/85

Subscribed and sworn to before me this 14th day of August 1985

Notary Public James R. Hatfield

Date Commission Expires



K.C.C. OFFICE USE ONLY
F Letter of Confidentiality Attached
C Wireline Log Received
C Drillers Timelog Received
Distribution
 KCC SWD/Rep NGPA
 KGS Plug Other (Specify)

RECEIVED STATE CORPORATION COMMISSION

Form ACO-1 (7-84)

AUG 16 1985

AUG 28 1985

Operator Name Petroleum Inc. Lease Name..... Garvey, Inc. "P" Well #..... 6.....

Sec..... 7..... Twp..... 16S..... Rge..... 42..... East West County..... Greeley.....

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached-static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken Yes No
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No

Formation Description
 Log Sample

DST #1 5010-5120 30-60-60-120

Name	Top	Bottom
Morrow	5032	
"A" Sand	5096	
Stockholm Sand	5129	
Mississippi	5166	

TOP CHART
 IHP - 2385
 IFP - 238-606
 ISI - 802
 FFP - 698-800
 FSI - 843
 FHP - 2385
 BHT - 141°
 REC. 1433' gassy free oil & 977' o&gcm

BOTTOM CHART
 2437
 740-793
 832
 740-845
 802

CASING RECORD New Used
 Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
.. Surface.....	...12 1/2...	...8 5/8...	...24#...	...1741...	H.C.	550	2%cc
.. Production...	...7 7/8...	...5 1/2...	...14# & 15 1/2#...	...5267...	H	250	3%cc
					50/50	240	10% salt

Shots Per Foot	Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
...2.....	...5099-5120.....		

TUBING RECORD Size 2 3/8 Set At 5171 Packer at Liner Run Yes No

Date of First Production 7/27/85 Producing Method Flowing Pumping Gas Lift Other (explain).....

Estimated Production Per 24 Hours	Oil	Gas	Water	Gas-Oil Ratio	Gravity
	205 Bbls	0 MCF	0 Bbls	0 CFPB	42.5

METHOD OF COMPLETION Production Interval

Disposition of gas: Vented Open Hole Perforation Sold Other (Specify)5099-5120.....
 Used on lease Dually Completed Commingled