

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23123-00-01
Spot: SESWNW Sec/Twnshp/Rge: 9-13S-18W
2894 feet from S Section Line, 4352 feet from E Section Line
Lease Name: DREILING D Well #: 2
County: ELLIS Total Vertical Depth: 3730 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	156	0	130 SX
PROD	5.5	3729	0	150 SX

Well Type: EOR UIC Docket No: E27840.1 Date/Time to Plug: 08/31/2011 11:00 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP
Proposal Rcvd. from: DONALD A BOWMAN Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 259-4154

Proposed Plugging Method: Ordered 405 sxs 60/40 pozmix - 4% gel - 600# hulls.
DV 1470' to surface with 550 sxs.
Packer stuck in the hole with three joints of tubing at approximately 3400'.
Shot off tubing - recovered 3300' of 2 3/8".
Casing leaks.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/31/2011 1:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing 3276'. Allied rigged to tubing and mixed and pumped 125 sxs cement with 300# hulls mixed in.
Pulled tubing to 2000'. Allied rigged to tubing and pumped 165 sxs cement with 300# hulls mixed in to circulate cement to surface.
Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 20 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Rigged to 8 5/8" - instant pressure to 1000#.

Perfs:

Top	Bot	Thru	Comments
3485	3536		LANSING-KANSAS

RECEIVED
SEP 02 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38250.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

Form CP-2/3

9/06/11

SEP 01 2011