

11-3

070606

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,030-~~6000~~
C SE NE, SEC. 13, T 18 S, R 32 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Beckley Well # 1

Operator: Thunderbird Drilling, Inc.
Name &

County Scott 150.96

Address Box 97
Ellinwood, KS 67526

Well Total Depth 4645 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 615

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 3 11 Year: 19 88

Plugging proposal received from Jim Rockhold
(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4641' Perfs at 4510-24'

1st plug sand back to 4460' and dump 5 sx cement on top of sand through bailer,

2nd plug at 1350' with 50 sx cement and 5 sx gel,

3rd plug at 660' with 50 sx cement and 5 sx gel,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 p.m. Day: 3 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4460' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped through casing with 50 sx cement and 5 sx gel at 1350',

3rd plug pumped 50 sx cement & 5 sx gel at 660',

4th plug pumped 10 sx cement at 40'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1350' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-17-88

Signed Dan Hobbs (TECHNICIAN)

INV. NO. 23011