

KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2125
Wichita, KS 67202

1-31

API NUMBER: 15-035-21,078 ⁰⁰⁰⁰

300'S C NE NE SECTION 26 TOWNSHIP 33 RANGE 5E
4320 FEET FROM S SECTION LINE
660 FEET FROM E SECTION LINE

OPERATOR LICENSE #5120
OPERATOR Range Oil Company, Inc.
NAME & 125 N. Market, Suite 1120
ADDRESS Wichita, KS 67202

LEASE NAME: Baker #1
COUNTY: Cowley
WELL TOTAL DEPTH: 3073' ^{99.87}
CONDUCTOR PIPE: 4 1/2" @ 3072'
SURFACE CASING: 8 5/8" @ 153'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A
OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: Mike's Testing & Salvage, Inc.
ADDRESS: Box 209, Chase, KS 67524 LICENSE: #6050

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 31 MONTH: Jan YEAR: 1996

PLUGGING PROPOSAL RECEIVED FROM: District II

COMPANY NAME: United Cementing PHONE: 316-321-4680

WERE: Sand back and spot 4 sacks cement at 3000'. Shoot 4 1/2" casing at 1800' and pull up to 250'. Circulate cement from 250' to surface. Pull casing out of hole and top off with cement.

PLUGGING PROPOSAL RECEIVED BY: Alan Nation
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE

COMPLETED: HOUR: 13:30 DAY: 31 MONTH: Jan YEAR: 1996

ACTUAL PLUGGING REPORT: Sanded back and spotted 4 sacks cement at 3000'. Shot 4 1/2" casing at 1800' and pulled up to 250'. Circulated cement from 250' to surface. Pulled casing out of hole and topped off with cement.

REMARKS: United #2984. 133 sacks cement. 60/40 Poz 2&Gel

I DID OBSERVE THIS PLUGGING.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 05 1996

INVOICED

DATE MAR 05 1996

Jerry Clark

(AGENT) CONSERVATION DIVISION
WICHITA, KS FORM CP-2/3
REV. 3/90

INV. NO. 44928

Dus