

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21951-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 13-10S-18W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: GARVERT B Well #: 1
County: ROOKS Total Vertical Depth: 3860 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD. PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3620		
SURF	8.625	289	0	180 SX
DVT		1482		550 SX
PROD	4.5	3802	0	275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2011 3:00 PM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/31/2011 7:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3400' - pumped 75 sxs cement with 200# hulls.
Pulled tubing to 2300' - pumped 75 sxs cement with 200# hulls.
Pulled tubing to 1200' - pumped 80 sxs cement - cement circulated.
POOH. Hooked to casing and pumped 10 sxs cement.
Max. P.S.I. 400#.
Hooked to Braden head and pumped 10 sxs cement.
Max. P.S.I. 500#.

Perfs:

Top	Bot	Thru	Comments
3634	3642		
3594	3600		
3585	3595		
3565	3569		
3545	3551		
3526	3532		
3510	3514		
3502	3506		

Remarks: ALLIED CEMENTING COMPANY-TICKET #38168.

Plugged through: TBG

District: 04

Signed _____

Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED

SEP 06 2011

Form CP-2/3

9/09/11

SEP 01 2011

KCC WICHITA