

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22563-00-00
Spot: SESESW Sec/Twnshp/Rge: 1-6S-23W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: JOHN KEMPER Well #: 3
County: GRAHAM Total Vertical Depth: 3780 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	251	0	165 sx
PROD	4.5	3776	0	125 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/29/2011 1:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: TOMMY ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Top of tubing 2110' - five joints left in the hole.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/29/2011 3:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2089' - pumped 150 sxs 60/40 pozmix - 4% gel with 250# hulls - circulated cement to surface.
Pulled all tubing Hooked to 4 1/2" casing - pumped 25 sxs 60/40 pozmix - 4% gel. S.I.P. 400#.
Hooked to 8 5/8" x 4 1/2" annulus. Pumped 50 sxs 60/40 pozmix - 4% gel. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3714	3717		

Remarks: CONSOLIDATED OIL WELL CEMENTING-TICKET #28183.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

RECEIVED

SEP 06 2011

Form CP-2/3

9/09/11

SEP 02 2011

KCC WICHITA