

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-24212-00-00  
Spot: SEWNWE Sec/Twnshp/Rge: 11-14S-19W  
4290 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: STADELMAN Well #: 4  
County: ELLIS Total Vertical Depth: 3846 feet

Operator License No.: 33723  
Op Name: PAUL BOWMAN OIL TRUST  
Address: 801 CODELL RD  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	294	0	170 SX
PROD	4.5	3830	0	447 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/01/2011 10:30 AM  
Plug Co. License No.: 33723 Plug Co. Name: PAUL BOWMAN OIL TRUST  
Proposal Rcvd. from: LOUIS "DON" BOWMAN Company: PAUL BOWMAN OIL TRUST Phone: (785) 434-2286

Proposed Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Plugging 09/24/1985 - Well was perfed at 1500' cemented with 200 sxs. Ran temperature survey. Top 700'.  
Method: 09/26/1985 -Perfed 650' cemented with 150 sxs. Cement circulated to surface.  
Casing leaks.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/01/2011 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 3350'. Allied rigged to tubing and pumped 100 sxs cement with 200# hulls mixed in.  
Pulled tubing to 1850'. Allied rigged to tubing and pumped 105 sxs cement with 250# hulls mixed in to circulate cement to surface.  
Pulled tubing. Rigged to 4 1/2" casing with a swedge and pumped 25 sxs cement.  
Max. P.S.I. 500#. S.I.P. 300#.  
8 5/8" instant pressure at 200#.

Perfs:

Top	Bot	Thru	Comments
3659	3667		ARBUCKLE

Remarks: ALLIED CEMENTING COMPANY-TICKET #38169.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN) *CM*

RECEIVED

SEP 06 2011

Form CP-2/3  
9/09/11

SEP 01 2011

KCC WICHITA