

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00830-00-00
Spot: W2NENE Sec/Twnshp/Rge: 13-2S-19W
660 feet from N Section Line, 990 feet from E Section Line
Lease Name: HUFFSTUTTER COOP UNIT Well #: 6-1
County: PHILLIPS Total Vertical Depth: 3388 feet

Operator License No.: 3182
Op Name: NPF ENERGY CORPORATION
Address: PO BOX 3827
TUSTIN, CA 92781

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217	0	75 SX
PROD	5.5	3353	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2011 9:00 AM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: PAT H. COCHRAN Company: NPF ENERGY CORPORATION Phone: (714) 730-7850

Proposed Plugging Method: Ordered 410 sxs 60/40 pozmix - 4% gel - 350# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/31/2011 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2851' - pumped 150 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 1700' - pumped 225 sxs 60/40 pozmix - 4% gel with 50# hulls to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 30 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 5 1/2" annulus. Pumped 5 sxs 60/40 pozmix - 4% gel.
Cement came out of Braden head.

Perfs:

Top	Bot	Thru	Comments
3286	3341		LKC

Remarks: COPELAND ACID AND CEMENTING-TICKET #37147.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

RECEIVED

SEP 06 2011

Form CP-2/3
9/09/11

KCC WICHITA

SEP 02 2011