

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-19062-00-00
Spot: NWENWSW Sec/Twnshp/Rge: 7-2S-18W
2630 feet from S Section Line, 4324 feet from E Section Line
Lease Name: HUFFSTUTTER Well #: S1
County: PHILLIPS Total Vertical Depth: 1246 feet

Operator License No.: 3182
Op Name: NPF ENERGY CORPORATION
Address: PO BOX 3827
TUSTIN, CA 92781

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1203		
PROD	5.5	1245	0	300 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 08/31/2011 12:00 PM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: PAT H COCHRAN Company: NPF ENERGY CORPORATION Phone: (714) 730-7850

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 4% gel - 200# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/31/2011 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 960' and tagged.
Pulled tubing to 920' - pumped 140 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 20 sxs 60/40 pozmix - 4% gel.

Perfs:

Top	Bot	Thru	Comments
993	1008		DAKOTA
968	977		DAKOTA

Remarks: COPELAND ACID AND CEMENT-TICKET #37148.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

RECEIVED

SEP 06 2011

Form CP-2/3
9/09/11

SEP 02 2011

KCC WICHITA