

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-21015-00-00  
Spot: SWNE Sec/Twnshp/Rge: 19-12S-33W  
1980 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: BECKMAN TRUST "A" Well #: 1-19  
County: LOGAN Total Vertical Depth: 4800 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	225	0	w/175 sxs cmt
PROD	4.5	4794	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2011 11:00 AM  
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.  
Proposal Rcvd. from: DAVE OLLER Company: MCCOY PETROLEUM CORPORATI Phone: (620) 532-9232

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Plug through casing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/23/2011 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

08/22/2011 - 8 5/8" surface casing set at 225' w/175 sxs cement.  
4 1/2" production casing set at 4794' w/150 sxs cement.  
TD 4800'. PBTD 4794'. Anhydrite 2638' - 2659'.  
Port collar at 2636' was not cemented.  
Experienced problems releasing slips from Braden head.  
Welder split head, slips wedge in 8 5/8" collar - cut off collar.  
Welded new 8 5/8" collar onto surface pipe.  
Shot production casing at 3427' - could not pull 4 1/2" casing.  
Shot production casing at 2672' - could not pull 4 1/2" casing - shut down for the night.  
08/23/2011 - Connected to 4 1/2" production casing - pumped 70 sxs cement.  
Displaced cement to 2572'. Max. P.S.I. 500#.  
Shot 4 1/2" production casing at 1650' - pulled one joint casing - pumped 100 sxs cement mixed with 200# hulls.  
Pulled production casing to 275' - pumped 40 sxs cement mixed with 50# hulls.  
Pulled casing to 40' - pumped 15 sxs cement - cement to surface.

Perfs:

Top	Bot	Thru	Comments
4662	4705		

Remarks: ALLIED CEMENTING COMPANY-TICKET 43394.

Plugged through: CSG

District: 04

Signed Darrel Dipman  
(TECHNICIAN) CM

RECEIVED ✓  
Form CP-2/3  
SEP 06 2011 9/09/11

AUG 24 2011

KCC WICHITA