

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-05302-00-03  
Spot: SWSWSW Sec/Twnshp/Rge: 1-6S-27W  
330 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: ADELL Well #: 601  
County: SHERIDAN Total Vertical Depth: 2030 feet

Operator License No.: 6113  
Op Name: LANDMARK RESOURCES, INC.  
Address: 1616 S VOSS RD STE 150  
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	240	0	w/240 sxs cmt
PROD	6	3808	0	w/300 sxs cmt

Well Type: EOR UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/26/2011 9:00 AM  
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC  
Proposal Rcvd. from: ALAN WALKER Company: LANDMARK RESOURCES, INC. Phone: (316) 755-3523

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 300# hulls.  
Plug through tubing.  
HAD A PENDING APPLICATION ON FILE - WELL WAS NEVER PERMITTED.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/26/2011 11:20 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

10 3/4" surface casing set at 240' w/240 sxs cement.  
6" production casing set at 3808' w/300 sxs cement.  
TD 4126'. Well plugged by Allied Cementing on 01/27/1998.  
Re-entered on 08/11/2011. Washed down to 2030'. Bit outside of casing.  
Operator elected to plug well.  
08/26/2011 - Ran tubing to 1716' - pumped 600# gel - followed with 100 sxs cement mixed with 300# hulls.  
Pulled tubing to 256' - pumped 45 sxs cement - cement to surface.  
Pulled tubing to surface.  
Connected to 6" production casing - pumped 5 sxs cement.  
10 3/4" surface casing was pre-plugged.

Remarks: CONSOLIDATED CEMENTING COMPANY-TICKET #28199.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

RECEIVED  
SEP 06 2011  
Form CP-2/3  
9/7/11  
9/6/11

AUG 26 2011

KCC WICHITA