

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23517-00-00  
Spot: NESWSWSW Sec/Twnshp/Rge: 28-18S-21W  
394 feet from S Section Line, 4631 feet from E Section Line  
Lease Name: ANSLOVER Well #: 1  
County: NESS Total Vertical Depth: 4723 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	250		WITH 150 SX CMT
DVT		1341		WITH 350 SX CMT
PROD	4.5	4600	0	WITH 100 SX CMT

Well Type: SWD UIC Docket No: D26206.0 Date/Time to Plug: 08/24/2011 2:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: DAVID HAYES Company: OIL PRODUCERS Phone: (620) 546-4456

Proposed Plugging Method: PLUG AT 4500' WITH 15 SX GEL & 50 SX CMT. PLUG AT 1500'. CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE  
Date/Time Plugging Completed: 08/24/2011 1:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

BOTTOM PLUG PUMP 200# HULLS, 15 SX GEL & 50 SX CMT W/3% CC. TOC @ 3300'. RAN TBG TO 1350' & CIRCULATED CMT TO SURFACE WITH 75 SX CMT. BACKSIDE WAS FULL.

Perfs:

Top	Bot	Thru	Comments
4600	4723		ARBUCKL

Remarks: \*\*COMPLIANCE ISSUE: FAILED MIT\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

*Steve Durrant*

(TECHNICIAN) *cc to WIC 9/7/11*

RECEIVED Form CP-2/3

SEP 07 2011 *9/09/11*

KCC WICHITA