

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23895-01-02
Spot: W2E2SE Sec/Twnshp/Rge: 23-18S-24W
1409 feet from S Section Line, 978 feet from E Section Line
Lease Name: UMMEL Well #: 4 H
County: NESS Total Vertical Depth: 4298 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 12
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4050		WITH 2 SX CMT
SURF	8.625	365		WITH 200 SX CMT
DVT		1658		WITH 275 SX CMT
PROD	5.5	4319	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2011 1:30 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: KYLA RANDA Company: MULL DRILLING Phone: (785) 798-0591

Proposed Plugging Method: SET CIBP THEN CEMENT CASING FROM 1600' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2011 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN CIBP TO 4050' & 2 SX CMT. SWAB CASING TO 1600'. TIE ONTO CASING & PUMP 175 SX CMT. PRESSURED TO 500# & HELD. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

RECEIVED
SEP 07 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED OIL WELL.

Plugged through: CSG

District: 01

RECEIVED

AUG 25 2011

KCC DODGE CITY

Signed

Michael J. Maier

(TECHNICIAN)

Form CP-2/3

9/09/11