

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20148-00-00
Spot: NWSW Sec/Twnshp/Rge: 36-27S-20W
2049 feet from S Section Line, 643 feet from W Section Line
Lease Name: ZIMMERMAN Well #: 1
County: KIOWA Total Vertical Depth: 4875 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	582		WITH 400 SX CMT
PROD	5.5	4871	2004	WITH 75 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2011 9:00 AM
Plug Co. License No.: 33939 Plug Co. Name: BLACKGOLD OILFIELD SERVICE LLC
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (316) 546-4801

Proposed Plugging Method: PLUG AT 4800' WITH 200# HULLS & 30 SX CMT. PLUG AT 1280' WITH 12 SX GEL & 50 SX CMT. PLUG AT 610' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/31/2011 9:55 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 200# HULLS & 35 SX CMT AT 4814'. 1ST PLUG AT 1292' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 603' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4871	4875		MISSISSIPPI
4859	4868		MISSISSIPPI

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Eric McLaren
(TECHNICIAN)

RECEIVED
SEP - 2 2011
KCC DODGE CITY

RECEIVED
SEP 07 2011
KCC WICHITA

Form CP-28
9/09/11