

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20164-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 21-14S-10W  
3347 feet from S Section Line, 4228 feet from E Section Line  
Lease Name: VOPAT G Well #: 7-A  
County: ELLSWORTH Total Vertical Depth: 2920 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comments                         |
|--------|-------|------------|-------------|----------------------------------|
| SURF   | 8.625 | 259        |             | 150 SXS CMT                      |
| T1     | 2.375 | 2779       |             | 68' OF TUBING, ETC. LEFT IN HOLE |
| PROD   | 4.5   | 2912       |             | 75 SXS CMT                       |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/24/2011 10:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP. Phone: (785) 483-1821

Proposed Plugging Method: NO MENTION MADE ON CP-1 OF CASING LEAK OR LEAKS, AND NO MENTION OF JUNK IN HOLE. THE 68' OF ABOVE ETC. LEFT IN HOLE AT 2779' INCLUDED 2 JTS OF TUBING, SEATING NIPPLE, AND MUD ANCHORS. ALSO, NO PERFS LISTED ON CP-1. GOT PERF INFO FROM KEN BUEHLER IN THE FIELD. KEN BUEHLER SAID THIS OLD WELL HAD PREVIOUSLY BELONGED TO GORSKI--THEY DIDN'T HAVE ANY RECORDS ON IT.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/24/2011 5:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ATTEMPT TO PULL TUBING--COULD NOT GET TUBING OUT. GOT LOOSE @ 2779'. PERFORATE AT 1200', 900' AND 310'. RUN TUBING TO TOP OF TUBING FISH AT 2779' AND PUMP 20 SX'S COMMON CEMENT. PULL 12 JT'S TUBING. LET SET FOR 1 HR. --RUN TUBING BACK DOWN--COULD NOT TAG CEMENT WITH TUBING -- RETAGGED TUBING FISH, THEN PULLED 1 JT. AFTER WAITING ANOTHER HOUR FOR CALCIUM CHLORIDE AND COTTON HULLS TO ARRIVE, ATTEMPTED TO PUMP CEMENT AGAIN--INSTANTLY PRESSURED UP TO 300#S. PULLED 12 JTS TUBING--ATTEMPTED TO CLEAR--PRESSURED UP TO 1800#S. PULL TUBING OUT COMPLETELY. HAD 8-9 JTS WITH CEMENT INSIDE, WHICH INDICATED THAT CEMENT WAS AT THE TOP OF TUBING FISH. RUN CLEAN TUBING DOWN TO 1200' AND PUMP 35 SX'S COMMON CEMENT WITH 2% CC AND COTTON HULLS. PULL 18 JTS TUBING OUT AND WAIT FOR 1 HR. TAG CEMENT AT 904' WITH TUBING. PULL TUBING TO 870' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 310' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2826 | 2838 | CSG  |          |

RECEIVED  
SEP 08 2011  
KCC WICHITA

Remarks: EMERGENCY WELL PLUGGING DUE TO CASING LEAK AND HFLD. QUALITY WELL CEMENT #5081. PERF TECH TICKET 8975.

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)