

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20446-00-01
Spot: S2S2NW Sec/Twnshp/Rge: 20-17S-10W
2947 feet from S Section Line, 3666 feet from E Section Line
Lease Name: SCHEPMANN Well #: 2 OWWO
County: ELLSWORTH Total Vertical Depth: 3152 feet

Operator License No.: 3942
Op Name: MONROE, ORVILLE DBA BIG "O"
Address: 2820 PASEO DR
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	228		150 SX
L1	4.5	3148		
PROD	5.5	3274		2166 PREVIOUSLY HAD BEEN PULLED

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/19/2011 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: _____ Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 08/19/2011 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND TO 2930' AND CAP WITH 4 SX'S CEMENT. CUT OFF CASING AT 1345' AND PUMP 35 SX'S CEMENT. PULL CASING TO 1000' AND LET CEMENT SET UP--WAIT 45 MINUTES. TAGGED CEMENT AT 1100'. PUMP 35 SX'S AT 1000', PULL CASING TO 270' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT & TOP OFF. USED 150 SX'S.

Perfs:

Top	Bot	Thru	Comments
3180	3186	CSG	
3144	3150	CSG	
3128	3136	CSG	
3110	3118	CSG	
3018	3022	CSG	
2990	2996	CSG	
2979	2986	CSG	
2964	2970	CSG	

RECEIVED
SEP 08 2011
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. COPELAND C-37157

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)