

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20438-00-00
Spot: SESWSW Sec/Twnshp/Rge: 21-17S-10W
322 feet from S Section Line, 4358 feet from E Section Line
Lease Name: SCHEPMANN Well #: 2
County: ELLSWORTH Total Vertical Depth: 3326 feet

Operator License No.: 33186
Op Name: LB EXPLORATION, INC.
Address: 2135 2ND RD
HOLYROOD, KS 67450

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3262		
SURF	8.625	268		175 SXS
PROD	4.5	3319		100 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/25/2011 11:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKISON Company: DS & W WELL SERVICING Phone: (620) 786-4258

Proposed Plugging Method: SEE BELOW. CP-1 INDICATES WELL AS IN POOR CONDITION

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: PARTIAL
Date/Time Plugging Completed: 08/25/2011 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU--CK BOTTOM. SET CIBP @ 3262' AND CAP WITH 2 SX'S CEMENT. PERFORATE AT 1325', 1000', AND 325'. RUN TUBING TO 1325' AND PUMP 35 SX'S CEMENT WITH 3% CC--PULL TUBING UP AND LET SET FOR 1.5 HRS. RUN TUBING BACK DOWN AND TAG CEMENT TO APPROX. 1145'. PULL TUBING TO 1000' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 325' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND CONNECT ON TO SURFACE CASING. PUMPED CEMENT AND PRESSURED UP TO 250#S. DISCONNECT AND TOP OFF CASING. USED APPROX. USED APPROX. 188 SX'S.

Perfs:

Top	Bot	Thru	Comments
3319	3326	OH	

RECEIVED
SEP 08 2011
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS TICKET #6690. ALLIED TICKET #37267. COMPLIANCE ISSUE-- DENIED TA-HFLD--IN WELL.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)