

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-041-20056-00-00  
Spot: NENWNENE Sec/Twnshp/Rge: 7-15S-1E  
4974 feet from S Section Line, 795 feet from E Section Line  
Lease Name: HAGG Well #: 1  
County: DICKINSON Total Vertical Depth: 2660 feet

Operator License No.: 5610  
Op Name: BRUCE OIL COMPANY, L.L.C.  
Address: 1704 LIMESTONE RD  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	170		100 SX
PROD	4.5	2658	1000	65 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2011 10:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: LEVI KOEHN Company: \_\_\_\_\_ Phone: (620) 241-2938

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/26/2011 10:00 AM KCC Agent: SHANE JONES

Actual Plugging Report:

SUNFLOWER PULLED RODS AND TUBING AND TAGGED BOTTOM. THEY DROPPED SAND. THE NEXT DAY THEY TAGGED SAND @ 2541 AND CAPPED IT WITH 4 SX. SUNFLOWER THEN RIPPED CASING AT APPROX 1000' AND LAID OUT 29 JTS OF 4.5". SUNFLOWER RAN IN AND TAGGED FLUID AT 270'. THEY DECIDED TO GO AHEAD AND CALL FOR REDIMIX AND TOP WELL OFF WITH SLURRY. SMOKY VALLEY CONCRETE OUT W/5 YDS SLURRY FILLED THE HOLE FROM 270' TO SURFACE. I TAGGED PLUG @ 2:00 PM AND FOUND IT DOWN 6' CREW WILL TOP IT OFF WHEN PLUGGING NEXT WELL. I SPOKE TO CREW ABOUT NOTIFYING ME OR THE DISTRICT OFFICE WHEN THEY CEMENT THE TOP PLUG SO WE CAN BE THERE TO WITNESS IT.

Perfs:

Top	Bot	Thru	Comments
2606	2611	CSG	

Remarks: DENIED TA DUE TO 10 YR RULE/SMOKY VALLEY CONCRETE TK #030044 FOR 5 YDS SLURRY MIX

Plugged through: OH

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED

SEP 08 2011

KCC WICHITA

Form CP-2/3

9/09/11

JK