

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24808-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 25-20S-13W
420 feet from S Section Line, 5141 feet from E Section Line
Lease Name: MARMIE Well #: 2-25
County: BARTON Total Vertical Depth: 3611 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	315	0	300 SX
PROD	4.5	3609	1780	150 SX

Well Type: OIL UIC Docket No: D28273.0 Date/Time to Plug: 08/29/2011 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/29/2011 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 4 sxs cement.
Cut casing at 1780' - pulled casing to 1550' - pumped 125 sxs cement with 300# hulls.
Pulled casing to 700' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 315' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 120' - circulated cement with 50 sxs cement.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3264	3268		
3244	3248		

RECEIVED
SEP 09 2011
KCC WICHITA

Remarks: QUALITY WELL SERVICE COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

9/13/11

AUG 30 2011